


420 Series Anti-Siphon Wall Hydrants




Repair & Replacement Parts

AIR-VENT ASSEMBLY	RUBBER-COATED HANDLE & SCREW	SPRING-LESS CHECK ASSEMBLY	GAP-SPACER WEDGE	420 SERIES 4" STEM ASSEMBLY	420 SERIES 6" STEM ASSEMBLY	420 SERIES 8" STEM ASSEMBLY
# PK1430 Includes green cap, housing, plunger, & O-ring (#'s 7-10)	# PK1295 Rubber-coated green oval handle (# 2) & stainless screw (# 1)	# PK2016 Replacement spring-less check assembly (# 6)	# PK1450 Replacement gap spacer, used to tilt faucet downward	# PK2004 4-inch hydrant stem assembly (# 3-6) (8" total length)	# PK2006 6-inch hydrant stem assembly (# 3-6) (10" total length)	# PK2008 8-inch hydrant stem assembly (# 3-6) (12" total length)

420 SERIES 10" STEM ASSEMBLY	420 SERIES 12" STEM ASSEMBLY	420 SERIES 14" STEM ASSEMBLY
# PK2010 10-inch hydrant stem assembly (# 3-6) (14" total length)	# PK2012 12-inch hydrant stem assembly (# 3-6) (16" total length)	# PK2014 14-inch hydrant stem assembly (# 3-6) (18" total length)



*For 420 series hydrants installed prior to 1999, use PK20_ SP stem assembly to replace old style stems that have a spring check assembly. Contact Arrowhead Brass for more details



If your faucet stem has a SPRING or does NOT measure to an even length, you may need an "SP" Stem

- SP Stems are 4-1/4" longer than the hydrant length (i.e. PK2004SP = 8-1/4")
- SP Stems should work as replacements for valve older than 1999 but often times may not work. SP or "special" stems are non-returnable & not covered under warranty
- Arrowhead Brass suggests replacing your faucet if it was installed before 2001. We can not guarantee that SP parts will work